



**CITY OF NIAGARA FALLS
ADDENDUM # 1
RFQ65-2011**

**Metal Fabrication and Installation
Niagara Falls History Museum**

This addendum shall form an integral part of the Request for Quotation (RFQ) documents for the above noted RFQ and shall be read in conjunction therewith. This addendum shall, however, take precedence over all requirements as it pertains to the particular and specific items noted below.

This addendum must be signed by the Bidder in the appropriate space and must be attached to the Bidder's quotation submission at the stated time of the closing of the RFQ or prior to this time. Quotation submissions not including this addendum may be rejected.

The RFQ requirements, contract requirements, specifications, schedules and drawings are amended as follows:

Refer to Page 2: Questions and Responses
Total pages this Addendum: 2

The Bidder shall take due notice of the above noted changes and make allowance for same in the quotation to be submitted to the City of Niagara Falls.

Company Name: _____

Bidder's Signature: _____

Date: _____

Questions and Responses

- Q1 What are the specifications for the expanded metal mesh for the modular steel wall racks.
A1 Expanded Metal open diamond size can be 25mm X 13mm, vertical direction, 18 gauge preferred. Also preferred is the typical raised pattern for better lateral support. Ametco Manufacturing Corp. 18 gauge, galvanized expanded metal no. 9, standard 3/4" - nominal dimensions: 3/4 " (SWD) X 1 1/2" (LWD) approx. **or equal.**
- Q2 How many wall racks are required per drawing STOR-1?
A2 Typical unit dimensions are indicated on drawing STOR-1 including details. Starting from the west wall and going clockwise, the quantities per single directional wall are: 3, 4 and 5.
- Q3 Regarding paint, is powder coating acceptable?
A3 Powder coating is acceptable.
- Q4 Modular Steel Wall #3 is circled pass where the plain view appears to show the racks. Are racks to be supplied for right to grid line 8b, or just the (3) as shown?
A4 Modular Steel Wall #3 is to start, (or clear) 6.625m from the north wall. It is clearly stated on drawing STOR-1. This group contains 3 units of 1.5m wide expanded steel frame **but must be butted tight against one another** to form a completed rack.
- Q5 What are the sizes of the bars for the back support on the thru steel wall rack?
A5 Angled steel bar min. nominal size: 1" X 1" X 3/16"
- Q6 What is the thickness of the welded steel anchor plate for the removable handrail?
A6 1/4" thick base minimum or as required.
- Q7 Note: Section 3.0 of the Specifications, Item 1/1.4 requires that all surfaces to receive 1 coat of primer and finish coat as noted. Drawing STOR-3 states lt. Grey. Are all materials to be painted lt. Grey for a finished coat? Is their a spec for the paint?
A7 The Specifications for paint have been revised to read:
Change from galvanized finish to non-galvanize panels, prime and painted 2 coats finish paint. Finish paint colour changed from grey to white (to match the storage system - not in contract). The paint colour to match Benjamin Moore colour Snow White #OC-66.

----- End of Addendum No 1 -----